



Specifications and Construction System Overview:

All materials to build standard barn

- Five sets of working blueprints and engineering calculations packet for your build site
- Master Material Ship List complete lumber take-off
- Complete structural materials package
- Hardware: thru-bolts, joist and rafter hangers
- Handcrafted pre-built door package

Arena framework & roof system details

- Treated rough-sawn posts, 6" for main timber-frame typical
- (rough-sawn posts engineered to be encased in concrete)
- Versa-lam beams 1¾"x for roof rafters
- Clear span engineered steel roof trusses
- 2"x cleat material (Hem-fir/standard and better rating)
- 2"x roof purlins and outrigger material (Hem-fir/standard and better rating)
- 2"x pre-cut purlin blocks
- 2"x Premium Pacific Northwest Douglas Fir (tongue and groove) 5' rub walls all around
- Rough-sawn T1-11 sheathing with tight knot Northwest cedar battens over gable end 2"x stud walls
- 1"x Tight knot Northwest cedar with 2"x fascia and barge boards (Hem-fir/standard and better rating)
- Two (2) sets of handcrafted pre-built 5'x6' swinging arena gates with hardware package
- One (1) handcrafted pre-built 4'x3'6" personal entry gate with hardware package

Breezeway package includes:

- Two (2) sets of 6'x9' pre-built (tongue and groove) track doors at each end of breezeway with trolleys, heavy-duty hardware package and black powder-coated track

Tack Room package includes:

- 2"x tongue and groove walls
- One (1) pre-built 4'x7' tongue and groove entrance door with hardware package

Barn Pros "Signature Service" provides:

- Barn Pros "Lifetime" Limited Structural & Hardware Warranty
- Service & Support: Barn Pros takes great pride in providing contractor and homeowner support throughout the build. Whether it be clarifying a connection detail, or providing insight on some tricks of the trade, we are here to ensure your build is successful.



Barn Pros Nationwide
14567 169TH DR. S.E. MONROE, WA 98272
PHONE: 1-866-844-2276

Club - ARENA KIT

NOTE:

While a Barn Pros building kit is extremely complete, there are items that will be provided by builder if applicable. These may include: roofing material and underlayment, fasteners (nails and screws for provided hangers), miscellaneous blocking (if not repurposed from supplied bracing), electrical, plumbing, drywall, insulation, concrete and labor. This list is not exhaustive and may vary based on model. Please consult a Barn Pros Project Specialist for clarification. All permits and related fees are purchaser's responsibility.

Materials:

- Lumber species listed are predominate in quantity. Small variations in species aren't uncommon and if included in your order would be indistinguishable from one another.
- All tongue and groove provided is Pacific Northwest Douglas fir "select grade" milled to both surfaces.
- Standard window packages provided (if any) are Jeld-Wen (vinyl) brand in Desert Sand.
- If products are unavailable in your area an equivalent will be sourced by Barn Pros.